

SALMONBERRY FLOAT REPLACEMENT -- IMPLEMENTATION PLAN

Project	Salmonberry basin float replacement, Rows M-P
Document	CHD-FAC-2026-003
Date	February 9, 2026
Prepared by	G. Fjell, Deputy Harbormaster
Construction window	January-March 2027 (off-season)

1. BACKGROUND

The Salmonberry basin (210 open slips) floats on Rows M through P date from 1994 and have lost freeboard steadily since 2019. The 2024-10 inspection measured end-of-row slips SB-1401 and SB-1428 at 59.2 and 59.4 ft as-built against 60 ft posted, and recommended re-posting after replacement rather than interim correction. The 2022-06-14 commission heard the design status at 60 percent; design is now complete and the grant pre-application has been acknowledged by the state boating programs office.

2. SCOPE

Replace 64 float modules across Rows M-P (slips SB-1301 through SB-1428), re-set 22 guide piles, and renew the row electrical feeders. The rotation takes slips out of service in four waves of 16, with tenants relocated within the basin under the temporary relocation policy. No change to the slip count (210) or to the posted dimensions except re-verification on completion.

3. SCHEDULE

- 2026-09: grant application filed (state boating programs).
- 2026-11: contractor pre-qualification; bid package issued.
- 2027-01-04: mobilization; Wave 1 (SB-1301-1316) out of service.
- 2027-01-03: four waves, 16 slips each, two weeks per wave.
- 2027-03-31: demobilization and as-built survey.
- 2027-04-15: dimensional verification with the measuring rail; posted dimensions re-issued before the 2027 season opens in April.

4. TENANT RELOCATION

Twenty-eight permanent tenants are affected. Each receives 60 days written notice, a relocation slip assignment within Salmonberry or Gullwing of equal or greater posted length, and one move assisted by the yard crew at District cost. Foot-month billing continues at the tenant's existing billed length; no re-measurement is triggered by a relocation.

5. BUDGET AND FUNDING

Engineer's estimate \$812,000. Funding: state grant application \$406,000 (50%), District moorage reserve \$310,000, facilities maintenance levy \$96,000. The 2027 budget carries the District share; the deferral of CR-0412 (user-identifier logging) is unrelated to this project and remains a separate line.

6. RISKS

- Grant timing: if the award slips past 2026-12, the construction window moves to January-March 2028; the 2027 season is unaffected either way.
- Pile condition below the mudline is unknown until pulling; a 10% contingency is carried.
- End-of-row creep (as at Ledgport Row F) will be addressed in the new pile layout with deeper embedment.

Prepared by: Greta Fjell, Deputy Harbormaster

Reviewed by: Reuben Calloway, Harbormaster